# BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

**Executive Engineeer**
**Byatarayanapura Division**
**B.B.M.P., Bangalore.**

## DRAFT TENDER SCHEDULE

**Name of Work: Improvements to Roads and Drains at Thindlu Colony, Kempegowdanagara and Surrounding areas in Ward No. 09, (Vidyaranyapura).**

| Sl. No. | Approved Qty. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 494.22 | Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. | Cum | 243.88 | Rupees Two Hundred Forty Three and Eighty Eight Paise Only |
| 2 | 793.80 | Removing and refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 111.30 | Rupees One Hundred Eleven and Thirty Paise Only |
| 3 | 119.07 | Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 742.00 | Rupees Seven Hundred Forty Two Only |
| 4 | 321.78 | Providing and laying **Plain cement concrete of mix 1:3:6 with with OPC cement @ 220kgs, with crushed 40mm** and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days etc complete as per specifications and directions of engineer in charge of the work. | cum | 5421.90 | Rupees Five Thousand Four Hundred Twenty One and Ninety Paise Only |
| 5 | 6.48 | Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6, edges of stones** chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work. | cum | 5811.98 | Rupees Five Thousand Eight Hundred Eleven and Ninety Eight Paise Only |
| 6 | 10.80 | Providing **ruled pointing 20 mm deep** to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 150.52 | Rupees One Hundred Fifty and Fifty Two Paise Only |
| 7 | 1891.20 | Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 979.44 | Rupees Nine Hundred Seventy Nine and Forty Four Paise Only |

| No. | Approved Qty. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 8 | 198.24 | Providing and laying in position **plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size** graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, for coping. Including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work. | cum | 5599.98 | Rupees Five Thousand Five Hundred Ninety Nine and Ninety Eight Paise Only |
| 9 | 1598.40 | Providing **precast slab of 100mm thick** including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge - Data rate | Sqm | 2337.00 | Rupees Two Thousand Three Hundred Thirty Seven Only |
| 10 | 12.96 | Providing **precast slab of 250mm thick** including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge - (Data rate Approved). | Sqm | 5418.00 | Rupees Five Thousand Four Hundred Eighteen Only |

28/08

**Executive Engineer**
**Byatarayanapura Division**
**BBMP, Bangalore.**

**Note:**

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))